

Gulf Stream[®]

Swimming Pool
Heat Pumps

PERFORMANCE

TOP RATED

EFFICIENCY



AHRI CERTIFIED™
www.ahridirectory.org

WARRANTY
10
YEAR
WARRANTY

10 YEARS PARTS / 5 YEARS LABOR

HI-5 SERIES
ONLY AVAILABLE IN FLORIDA
SEE COMPLETE WARRANTY FOR DETAILS



WWW.GULFSTREAMHEATPUMP.COM



PERFORMANCE AND EFFICIENCY:	INTELLIGENT CONTROL: (Additional wiring may be required)
------------------------------------	--

4-Sided Evaporator Coil
Super-sized for maximum efficiency
Higher Performance in all weather
Engineered for a smaller footprint

2" Full Flow Titanium Heat Exchanger
Pipe size does not reduce once inside the unit
Maximum water flow design for higher efficiency
Lifetime titanium warranty against corrosion

Ultra-Quiet Design
Quiet scroll compressor
Commercial grade fan motor designed for quiet operation
Only 56db while in operation

Ultimate Warranty
Industry Best 5: Years Labor 10 Years Parts

GPS Affordable Spa Automation
Isolates the spa, energizes the pump & switches thermostats
Plug-ins for 2 actuators
Wireless options available

Solarwise Solar Heating Controller
Solar pool automation for hybrid pool heating control
Prioritizes solar pool heating for maximum efficiency
Actuator Plug-in & roof sensor connections

Compatible with all external Automation
Simple connection and programming
Seamless integration with all major brands of automation

Even Heat
Maintains the perfect temperature 24-hours a day

ADVANCED ASSEMBLY AND TESTING

Helium Leak Testing
100-times more accurate than the competition
Ensures optimized performance in every unit

Mass Flow Charging
The most accurate way to ensure proper refrigerant charging
Computerized accuracy to 1/100th of an ounce

Rust Proof ABS Cabinet
Strong ABS cabinet designed for harsh climates
UV inhibitors added for lifetime durability
Avoid the metal-cabinet regret

Comprehensive Final Run Test
Computerized quality control testing cannot be bypassed
Every-component in every-unit tested every-time
A "Perfect" unit every time for the ultimate peace of mind

UNIT SPEC	HI-110	HI-125	HI-150
BTU/COP AHRI HIGH TEST POINT(80/80/80) LOW TEST POINT (50/63/80)	110,000/6.2 66,000/4.1	117,000/6.3 74,000/4.1	136,000/6.0 85,000/4.0
MIN AMPS / MAX BREAKER	37/40	37/50	37/50
WEIGHT (SHIPPING)	215 LBS (243 LBS)	237 LBS (265 LBS)	239 LBS (267 LBS)
DIMENSIONS (SHIPPING)	31 X 31 X 38 (33 X 31 X 43)	31 X 31 X 42 (33 X 31 X 47)	31 X 31 X 42 (33 X 31 X 47)



WWW.GULFSTREAMHEATPUMP.COM

